## **VIBRATION ISOLATION ROOF CURB FOR YORK UNITS PROVENT P/N** Α **FEATURES:** Roof curb sides and ends are 16 ga. galvanized CBISPRL19\*\* 8" ZX, ZY 08-12; ZX 14; ZY 07 steel. CBISPRL22\*\* 11" Fully welded construction. CBISPRL25\*\* 14" \*Note: Spring configuration must be added to Gasketing package provided. part number at time of order. Heat treated wood nailer provided. Insulated deck pan provided. Pitched curbs and taller curbs are available. 1 1/2" TYP CalDyn OSHPD pre-approved 2" deflection seismic restraints. (OPA-0070) JQA. 84" O.D. NOTES 53" O.D. Attach ductwork to roof curb. Flanges of duct rest on top of curb. Support ductwork below the curb. 81 1/4" O.D. curb 50" I.D. 78 1/4" Í.D. 15 13/16" S/A R/A UNIT BASE RAIL 40 3/16" "Ė' Total Height ISOLATOR RESTRAINT FULL PERIMETER WOOD NAILER Base Height **TYPICAL** 16 GA CURB SIDE VIEW DETAIL JOB NAME: FORM NO: PART NUMBER: 3847 WABASH DR. ProVent **MIRA LOMA, CA 91752** ADDRESS: **CBIS-118 CBISPRL SERIES** DATE: REV: PHONE (951) 685-1101 NOTES: FAX (619) 872-9799 4/14/2014

**WEIGHT** 

330 Lbs.

345 Lbs.

360 Lbs.

19"

22"

25"

DRAWN BY:

CNG