EST. For wood, concrete and steel attachment see Roof Anchorage Detail, Form No. CB-62. STRUCTURALLY CALCULATED VIBRATION ISOLATION PROVENT P/N Α WEIGHT **ROOF CURBS FOR YORK UNITS** CBISCSUN367218\*3 Welded Isolation springs housingare 8" 18" 260 Lbs. standard. For bolted spring housing, ZR, XN, XP 036-060, neoprene pads and spring cups see CBISCSUN367221\*3 280 Lbs. 11" 21" ZE, ZF 036-072 Weldment and Bolting Detail, Form No. CB-61 CBISCSUN367224\*\* 14" 24" 300 Lbs **FEATURES** \*\*Note: Spring configuration must be added to part number at time of order Roof curbs sides and ends are 14 ga. 36 3/4" O.D. Fully welded construction. 33 1/4" I.D. Meets seismic requirements for the following codes: CBC 2019 IBC 2018 72 1/2" Ó.D. Gasketing package provided. 69" I.Ď. Heat treated wood nailer provided. 19 1/2" insulated deck pans provided. Pitched curbs and taller curbs are available. CalDyn OSHPd pre-approved seismic restraints. (OPM-0401-13), (CQA). **NOTES** Attach ductwork to roof curb. Flanges 19 1/2 of duct rest on top of the curb, Support ductwork below the curb. Thru the curb utillities are available. Contact you York distributor or Provent directly. 33 1/4" I.D. (4) #10 TEK SCREWS-UNIT BASE RAIL 14 GA UPPER RAIL ATTATCH TO UNIT WITH (4) #10 x 6" TEK SCREWS EACH HOLD DOWN 14 GA UNIT HOLD DOWN (2) PER LONG SIDE (1) PER SHORT SIDE **CQA ISOLATOR RESTRAINTS** "B" TOTAL HEIGHT 35" MAX WITH PITCH) (2) EACH LONG SIDE (1) EACH SHORT SIDE SE 3578 "A" BASE **FULL PERIMETER WOOD NAILER CURB HEIGHT** STIFFENER 16 GA x 7" x 1 1/2" 75" O.D. AT EACH ISOLATOR 39 1/4" O.D 14 GA. CURB **PROFILE DETAIL** FORM NO: PART NUMBER: SUBMITED TO: ProVent 3847 WABASH DRIVE MIRA LOMA, CA 91752 COMPANY: \_ CBISC-03 JOB NAME: \_ PHONE (951) 685-1101 DATE: REV: DRAWN BY: FAX (619) 872-9799 EQUIPMENT: \_\_\_\_\_ 4/20/2022 4 **FMM** NOTES: